

EBARA

# Model EPD / OPTIMA Pro Drainer™ sump, drainage



EBARA

EBARA Fluid Handling

an EBARA International Corporation company

# Model EPD/OPTIMA

## Features

- High quality stainless steel (*Note:* Optima has Noryl impeller)
- Available in 1/3, 1/2, 3/4, 1, 1 1/2 HP models
- Single and three phase models available
- Air filled, continuous duty rated, permanent split capacitor motors
- Built-in thermal protection with automatic reset
- Built to operate whether fully or partially submerged
- Oil lubricated double mechanical shaft seal (1/2 - 1 1/2 HP models)
- Temperature rating to 122°F/50°C; 140°F/60°C intermittent duty
- 20' UL/CSA approved, water resistant #16 AWG cord
- Capacities to 88 GPM, heads to 62 feet
- Optima and EPD slimline automatic models can operate in a 12" diameter or 8" x 8" square basin


## Applications

- Residential
- Commercial
- Industrial
- Drainage
- Seepage
- Effluent/containment transfer
- Waste water (from trays, wet bars, washing machines)
- Empty water storage structures
- Decorative fountains
- Irrigation
- Mound systems, leach fields
- Move water/effluent to sewage systems



*\*Note: UL and CSA listed; Model Optima UL certified only.*

## EPD, Optima selection chart



### EBARA Fluid Handling

1651 Cedar Line Drive • Rock Hill, SC 29730 • telephone: (803) 327-5005 • fax: (803) 327-5097

[www.pumpsebara.com](http://www.pumpsebara.com)

© 2011 EBARA International Corporation, All rights reserved.

EFHEPD 1011